MYSORE DIVISION.

Dated 13th March 1908.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Mysore Division, up to 7th April 1908, for improving and extending the Koppa tank sluice channel, Registered No. 132, Nagamangala Taluk.

An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of 190 .

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's office at , between the hours of

3. Tenders should be submitted on printed forms, which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rupees (100) one hundred in cash or Government promissory notes, as earnest money, and be superscribed "Tender for improving and extending the Koppa tank sluice channel, Registered No. 132, Nagamangala Taluk," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Particulars of work.	Per.	Quantity.
Improving the existing channel.		
Earthwork ordinary soil, clearing silt	C. yd.	1,331
Earthwork embankment	Do	2,730
Providing a cross scouring sluice in the 4" relieving weir with teakwood shutters	L S.	
Removing and refixing the existing bank grade stone with numbering, etc.	Each	13
Repairing and refixing new bed grade stones at every ½ furlong ...	Do.	16
Clearing site and refilling after the construction of Madavois ...	L. S.	
Burnt brick in surki mortar	C. ft.	86
Plastering with surki mortar, 2 coats	Sqr. *	·82
Cost of concrete pipes average including carting and fixing, etc., complete.	Each	6
* Total for 1 Madavoi.		
Constructing five masonry Madavois of the above description.		
Raising relieving weir by 6 inches	L. S.	
Extension of channel.		
Earthwork, gravelly soil, cutting channel	C. yd.	2,563
Earthwork embankment with consolidation	Do	11,977
Turfing	S. yd.	7,784
Removing boulders, etc.	L. S.	
Revetment	C. yd.	107
Bed grade stones	Each	15
Bank grade stones	Do	16
Mile stones	Do	2
Madavois.		
Excavation for foundation and filling in including tamping, etc. ...	L S.	
Surki concrete	C. ft.	34
Cement concrete	Do	20
Kadapa slabs flooring	Sqr.	·09
Sheet iron pipe 4 inches diameter	R. ft.	13
Shutter including locking arrangements, etc.	L. S.	
Centering charges for cement articles	Do	
Total for 1 Madavoi ...	...	
For six Madavois of the above description	...	
Aqueducts of 2 vents 6′×6′ at 6/1 mile.		
Burnt brick in surki mortar	C. ft.	183
Plastering with surki mortar	Sqrs.	3·24
Benching rock	C. yd.	
Concrete in surki mortar	C. ft.	
Stone in surki mortar	Do	2
Stone uprights, etc.	Do	
Burnt stone slab, dressed	Sqr. ft.	1
Pointing with surki mortar	Sqr.	1·75
Clearing approaches, etc.	L. S.	
Banking in both sides of aqueduct	Do	

Particulars of work.	Per.	Quantity
Aqueduct of 1 vent 9′ × 10′ at 3/2 mile.		
Earthwork	C. yd.	21
Revetment	Do	5
Burnt brick in surki mortar	C. ft.	17
Plastering with surki mortar	L. S.	
Concrete in surki mortar	C. ft.	100
Stone in surki mortar	Do	859
Pointing with surki mortar	Sqr.	3·80
Banking in both sides of aqueduct	L. S.	
Armoured concrete including armouring work	C. ft.	91
Tunnel on 3/63 mile.		
Revetment	C. yds.	6
Plastering with surki mortar	Sqr.	3·09
Stone in surki mortar	C. ft.	588
Burnt stone slab dressed	S. ft.	113
Cutting and refilling road and excavating foundation for abutments, etc...	L. S.	
Guard stones	Each	4

B. SUBBA RAO,
Exec. Engineer.

GOVERNMENT CENTRAL BOOK DEPOT.

Notice dated 21st February 1908.

The following book is available for sale at the Government Central Book Depot, Bangalore

Paper Sloyd—For Primary Grades, by Anne Rich : price per copy Rs. 2-4-0.

Notice dated 7th March 1908.

The following is a list of books and Government Proceedings available for sale in the Government Central Book Depot, Bangalore :—

Name.	*Price.* Rs.	a.	p.
General Administration Report for 1906-07, English ...	... 1	0	0
Mysore Code, Vol. III	... 4	0	0
Proceedings of the Representative Assembly, 1907, English ..	... 1	0	0
Do do Kannada ...	... 1	0	0
Civil Procedure Code, English	... 1	0	0
The Indian Limitation Act, 1877, Kannada	... 0	5	6
Revised Mysore Government Savings Bank Rules, English ...	... 0	4	0
Revenue Administration Report, 1902-03	... 0	5	6
Do do 1903-04	... 0	5	6
Do do 1904-05	... 1	0	0
Do do 1905-06	... 0	12	10
Forest do 1902-03	... 0	7	0
Do do 1903-04	.. 0	7	0
Do do 1904-05	... 0	7	0
Do do 1905-06	... 0	7	0
Government Proceedings No. J. 2527—Cts. 104-07-16. Reviews the analysis of the average duration of uncontested original suits in the several Civil Courts in the State	... 0	0	9
Government Proceedings No. 7191-204—M. L. 379-06-8. Requesting the Sanitary Commissioner to submit a definite programme for the sanitary works to be executed in Municipal towns and rural tracts, in connection with the drainage projects of the Seringapatam Town	... 0	0	9
Government Proceedings No. R 4695-9—L. R. 98-07-5. Commenting on the resolution of the United Planters' Association of S. India to the effect that the position of prospective rubber-planters in Mysore is unsatisfactory and that the disabilities under which the rubber-planting industry is labouring should be removed	... 0	2	0
Government Proceedings No. R. 4706—R. M. 141-07-1. Requesting the Revenue Commissioner in Mysore to take needful action to give effect to the promise conveyed in the reply of Government to Subject No. 215 of Dasara Representative Assembly of 1907, relating to orders of Deputy and Assistant Commissioners being issued in Kanarese	... 0	0	6